# Bangladesh Red Crescent Society

National Head Quarter (NHQ)
684-686, Red Crescent Sarak, Bara Moghbazar, Dhaka 1217.
PABX: +88-02-48310188-9, Ext: 222, 258, Direct: +88-02-8333430, web: www.bdrcs.org

# INVITATION FOR TENDER

| | |
|---|---|
| 1. Invitation Reference, Tender ID No and Date | Pro.(Log.)/916/2026, date: 01/11/2026, Tender ID no.: 24/2026 |
| 2. Procuring Entity Name | Director and Head of Operation, PMO BDRCS |
| 3. Name of Requisition Department | Health |
| 4. Procurement for | Mother and Health Care Center (MCHC), Hajom Para Teknaf |
| 5. Procurement Category | Works and Physical Service |
| 6. Description of Tender | Repair and maintenance work of infrastructure of MCHC teknaf |
| 7. Procurement Method | Open Tendering Method (OTM) |
| 8. Source of Funds | International Federation of Red Cross (IFRC) |
| 9. Purchase of Tender document | Tender documents and schedules with detailed information are available at the Bangladesh Red Crescent Society (BDRCS) website: www.bdrcs.org. Tender Schedule Download Link: https://bdrcs.org/tender/<br>**Tender Schedule Purchase Process:**<br>• Interested bidders are requested to collect the tender documents within the stipulated timeframe from the mentioned link/BDRCS website.<br>• Tender Schedule Purchase Fees (Non-refundable) is **BDT 1000.00**<br>• To Purchase Tender Schedule, Please make PAYMENT to BDRCS bKash Merchant Account No: **01894806393**<br>• Please insert the reference number **(Log.)/916/2026** while making bKash Payment.<br>• Please mention the bKash transaction reference number on top **Table-1** in tender schedule.<br>Failure to include the bKash transaction reference number may result in the disqualification of your bid. |
| 10. Tender Schedule available | From 01-11-2026 to 15-11-2026 |
| 11. Tender Submission Date and Time | 15-11-2026 at 12:00 pm<br>(If not possible for any unavoidable circumstance tender will be opened next office day at the same time & venue.) |
| 12. Tender Opening Date and Time | 15-11-2026 at 12:15 pm |
| 13. Address of Tender Submission & Opening | Logistics Department, National Headquarters, BDRCS, 684-686 Red Crescent Road, Bara Maghbazar, Dhaka-1217. |
| 14. Place/Date/Time of Pre-Tender Meeting | **11:00 AM on 10 November 2026** in the Logistics Department Meeting Room, Population Movement Operation (PMO), Motel Labone, Coxs Bazar. |
| 15. Eligibility of Tenderer | Construction firms or firms with similar relevant experience in renovation/retrofit works, including the repair and maintenance work of infrastructure, will be given preference. |
| 16. Brief Description of works/ Related Services | As per tender documents |
| 17. Tender Security Amount | 2.5 % of the Total quoted amount |
| 18. Completion Time (In days) | 30 (Thirty) days |
| **The Bangladesh Red Crescent Society reserves the right to accept or reject any or all tender or split the order without assigning any reason whatsoever and will not be bound to accept the lowest bid.** | |

Size: 3 col x 6”

**Akram Ali Khan**
Director and Head of Operation, PMO

# Bangladesh Red Crescent Society

**Population Movement Operation**

**Motel Labonee, Motel Road, Cox's Bazar-4700.**

Date: 01/11/2026

## TENDER SCHEDULE

The Bangladesh Red Crescent Society invites sealed tenders from the Supplier/Importer/Manufacturing Company for "**Repair and Maintenance Work of Infrastructure of MCHC Hajom Para Teknaf"** for Health Sector as per following:

1. **Scope of Supply:**

| Sl No | Title Of the Repair and Maintenance works |
|---|---|
| 1 | Repair and Maintenance Work of Infrastructure of MCHC |

2. **Specification:** The above Repair and Maintenance works must be fit for intended use and meet the BoQ specification accordingly. The Repair and Maintenance materials must be of sound, fair and marketable quality. Detailed specification/BoQ is attached in **Annexure-1.**

3. **Availability of Tender Document:** Tender documents/schedule with detailed information will be available at Finance Dept. of BDRCS PMO; Cox's Bazar Office during **9:30 am to 04:00 pm** on office hours latest by **November 12, 2026,** (Except Friday and Saturday) by a non-refundable fee cash **Tk. 1,000/-** in favour of Bangladesh Red Crescent Society through application of your firm letterhead. Mentionable that "Tender documents/schedule purchased money receipt" must be accompanied with tender/quotations and if not tender may be rejected.

4. **Tender Submission:** Sealed Quotations/Tender documents (with signed specification-annex-1 and price format-annex-2) along with sample (N/A) will be received in the tender box at Logistics Dept. of BDRCS, PMO office, Cox's Bazar latest by 12:00 pm on **November 15, 2025,** marking on top of envelop- **"*Tender for* Repair and Maintenance work of Infrastructure of MCHC** and must be accompanied by all the information/documents as per tender. Tender documents will be opened **at 12:15 pm on November 15, 2026,** at the Logistics Department meeting room of BDRCS PMO Office, Cox's bazar in presence of bidders if any. But if not possible for any unavoidable circumstance tender/quotation will be opened next office day at the same time & venue.

5. **Delivery Destination: T**he Repair and Maintenance works are to be delivered to **BDRCS MCHC Center, Hajom Para, Teknaf; Cox's Bazar** Supplier shall be responsible for all costs arising from forwarding and delivering of construction works to actual point of delivery including loading, unloading, transportation and insurance. The BDRCS authority will inform the selected supplier regarding of the detail delivery plan (in written) and the supplier will be fully responsible to deliver the Materials as per the plan.

6. **Packaging and Marking:** All the individual items for one family/package must be packed in good condition in a packet (packet/packaging as per specification). The items must be in good condition to be transported, loaded and unloaded without any damage to the products up to the final destination (as per clause-06).

7. **Delivery Period:** Repair and Maintenance works must be delivered at the delivery destination at the soonest but within a maximum period of **30 days** from the date of signing of purchase order, as per delivery schedule mutually agreed without any reason.

8. **Price:** Price should be quoted in the given format in **annexure 1**, and as per quantity in BDT (Bangladeshi Taka) inclusive of all costs loading, unloading, transportation, packing, marking (Logo), text, taxes, duties, levies and insurance etc. respectively for delivery at the destination mentioned above in clause -6.



01/11/2026

9. **Income Tax & VAT** will be deducted at source as per Govt. rules at the time of final payment. In case of any arithmetical discrepancy between the unit rate and the total amount quoted, then the unit rate shall prevail both for the evaluation of quotations and for the subsequent supply.

10. **Required Documents/Certificates:**
    a. Valid Trade License
    b. Valid TIN Certificate
    c. VAT registration certificate.
    d. Signed copy of all tender documents by the tenderer (pages)
    e. Tender Schedule purchased receipt.
    f. Bank solvency Certificate

10. **Above all the administrative document and evaluation sheet must be attached with the technical Offer in one envelope and sealed.**

11. **Financial Offer into another Envelope with sealed and write in the top : Financial Offer.**

**Note: Technical offer and financial offer separately entered into another Outer Envelope and sealed the outer envelope and submit to BDRCS tender Box. In the top of the Envelope must be put the title" Tender for the Repair & Maintenance of Infrastructure of MCHC Teknaf.**

**If you do not follow the Instructions, your bid will be non-responsive, and you do not claim in this regard.**

12. **BDRDCS technical team evaluate the tender is following: Marking categories.**

| **A. Technical Qualification (30 Marks)** | |
|---|---|
| **Description** | **Marks** |
| **Information about technical person (Engineer/Site supervisor list)** | **10** |
| **Work Plan** | **10** |
| **Equipment list** | **10** |
| **Quality Assurance and Quality Control System** | **10** |
| **Safety Measures of Workers** | **5** |
| **Total** | **45** |
| **B. Company Experience** | |
| **Description** | **Marks** |
| **Minimum 2 years' experience in repair, renovation, maintenance or civil construction works** | **10** |
| **Similar works completed during the last 2 years** | **5** |
| **Value of works executed during the last 2 years** | **10** |
| **Average annual turnover based on the last 2 years** | **5** |
| **Past Experience with BDRCS/IFRC/PNS/INGOs/Government organizations** | **5** |
| **Total** | **40** |
| **C. Financial Offer (20 Marks)** | |
| **Description** | **Marks** |
| **Lowest Evaluated Responsive Bid** | **20** |
| **Total** | **100** |

12. **Samples/Pre-Bid Meeting:** BDRCS is mentioned the pre-bids meeting at tender invitation of **November 10, 2026, Time: 11.00 am BDRCS; PMO; Cox's Bazar**, If you won't be unable to join with us physically kindly write the email to us the following: Logistcspmo@bdrcs.org and BDRCS Management may arrange the meeting with online.



07/11/2026

**13. Validity:** Your offer must remain valid for **3 months** from the date of the offer. If the BDRCS needs to extend/increase the **construction** delivery period, the selected supplier must deliver the **works** as per the same price and BoQ/Specification.

**14. Inspection:** Supplied Construction **Materials** must meet the required specifications and test (if)/inspection results must meet to our standard specifications mentioned in this tender documents. Quality and quantity inspections will be carried out at the supplier's place before the. If the supplied Construction **Materials** do not meet the specification, will not be accepted by the BDCRS and in that eventuality, the supplier must replace the goods and bear the inspection cost and/or other losses/penalty, as may be fixed by the buyer.

**15. Liquidated Damages**: Arrival of goods after agreed delivery schedule must become under damages/penalty from the invoice **per day up to maximum 0.5% of the total value** of the contract for a maximum period of 7 days. If the supplier fails to deliver the goods after 7 days of the delivery period, the contract will be null, and void and the security money will be forfeited besides other action for non-performance of the contract. ***If you deny/fail to receive the work-order/agreement/purchase order within 03 working days, then your earnest money will be forfeited.***

**16. Payment:** Within 30 days from the date of submission of invoice/bill with all supporting documents i.e. commercial invoice, duly signed delivery challan, **Good Received Note (GRN)** by the in-charge warehouse/field personnel (BDRCS) and the **satisfactory Completion Certificate report from the inspection team from the technical team/SPC members.**

**16. All price offers should clearly state the following**:

a) Unit Price of the item, and total amount for the supply (including words/language)
b) Price should be net after deduction of any discount and should be inclusive of all cost, taxes, VAT and duties (Please refer to clause 6 and 7).
c) **Confirm dates for starting and completion of delivery at delivery points along with the *detail delivery plan/schedule.***

**17. Pertinent Information:**

1. Goods are required for the DRR Project in BDRCS under DRR Department, BDRCS, PMO Office for community/FDMN people. Therefore, it is essential that goods are delivered as a matter of emergency.
2. The BDRCS authority may split the order among suppliers if necessary.

**18. Bid Amount:** Bidders must submit along with their quotation **2.5%** of the total quoted amount (BDT) as **earnest money/bid money** in the form of Pay Order/Demand Draft (in favour of "**Bangladesh Red Crescent Society"**) from any scheduled Bank. Cheque will not be accepted. Bid amount of unsuccessful bidders will be returned after expiry of the quotation validity period.

**19. Security Money /Performance Bond:** The successful bidder(s) must deposit **7.5%** of the total value of the order as performance security in the form of a **Demand Draft/Pay Order or Bank Guarantee** from the schedule Bank in favor of **BDRCS Population Movement Operation"** at the time of signing the purchase agreement/order. This security money/performance bond will be refunded after **one-month** defect liability period/or satisfactory completion of the total supply. If the contract is partially cancelled due to the non-performance by the supplier, all rights of refund of security money will be forfeited. If the supplier failed to supply the goods as per the contract due to non-availability of the products or any other reasons in the market, the security money will be forfeited.

**20. All or None Clause**: BDRCS reserves the right to accept or reject any or all offers, and the lowest bid need not be accepted without assigning any reason. Failure to comply with any of the above requirements will justify rejection of the quotation.

Should your offer be accepted, you will be required to sign, stamp and return our formal Purchase Contract(s) confirming your acceptance of the agreed terms and conditions as per this tender documents.

**21. Conditions/Last Date for submitting offers:** Your quotation/**offer** and the samples must be submitted in the 'Tender Box' located in the following address latest by ***November 15, 2026, at 12:00pm. To (address):***



07/11/26

Head of Operation (PMO)
**Motel Labonee, Motel Road, Cox's bazar**
PMO, BDRCS, Cox's Bazar-4700

.**Please acknowledge this request and indicate your intention to bid.**

**22. Tender opening: On *November 15, 2026, at 12:15:00 pm*** in the BDRCS Logistics Department meeting room, 117, PMO office; Cox's Bazar in presence of one representative of each bidder (if any).

**23. Principles of Conduct Clause:** The Contractor seeking to work with the BDRCS shall respect the following principles:

a. **Anti-Corruption Clause: "**No offer, payment, consideration, or benefit of any kind which could be regarded as an illegal or corrupt practice shall be made -- neither directly nor indirectly – as an inducement or reward in relation to tendering award of the contract or execution of the contract. Any such practice will be grounds for the immediate cancellation of this contract and for such additional action civil and/or criminal as may be appropriate. (At the discretion of the **BDRCS**, a further consequence of any such practice can be the definite exclusion from any tendering for projects funded by the **BDRCS)**.
b. **Business Ethics:** The Contractor is expected to maintain the highest degree of business ethics when working with the **BDRCS**.
c. **Transparency of information provision:** Contractor shall not be involved in any fraudulent activities, misrepresent information or facts for the purpose of influencing the selection and contract awarding process in its favour.
d. **Fair competition:** Contractor shall not be involved in any corrupt, collusive or coercive practices.
e. **Officials not to benefit:** The Contractor represents and warrants that no official of the BDRCS has been, or shall be, admitted by the Contractor to any direct or indirect benefit arising from this Request for Quotation, Work Order/Contract or the award thereof. The Contractor agrees that breach of this provision is a breach of an essential term of this Work Order/Contract.

If at any time during the supply process the BDRCS determines that the Contractor/supplier is in violation of the above-mentioned principles, that Contractor's request for registration or bid may be rejected as ineligible. In such case, all costs in relation to the cancellation of contracts shall be borne by the Contractor.

**24. Confirmation:** Please acknowledge your acceptance to bid by signing on the Tender Documents/Schedule along with the terms and conditions and attach it with your quotation.

**25. General condition:** BDRCS reserves the right to accept proper quality and increase or reduce the quality of goods and cancel the order in any violation of the terms and condition.

**N.B**. Kindly submit your best firm offers as negotiation will not be entered into.

With Thanks,

Akram Ali Khan
**Director & Head of Operation**
Bangladesh Red Crescent Society

**Annex-1 – BoQ attached with the tender schedule.**

## Bangladesh Red Crescent Society

Bidder Signature:

Name:----------



01/11/26

SL-17
MCHC
Teknaf

# Bill of Quantity (BoQ)

## Treatment of Roof , Construction of Guide wall and Other Repairing & Miscellaneous works at MCHC, Teknaf.

| SL No. | Description of Items | Unit | Quantity | Unit Rate (BDT) | Amount (BDT) |
|---|---|---|---|---|---|
| **A. Roof Treatment** | | | | | |
| 1 | **Patient Stone Dismantling:** Dismantling of Existing patent stone as per requirement with suitable device, as per direction of engineer in charge. | Sft | 950 | | - |
| 2 | **Rubbish Carrying:** Carrying rubbish, taking up all sorts of bricks, brick-bats and rubbish gravel chips, loading and unloading at both ends including supply of tools and plants etc, all complete and accepted by the Engineering in-Charge. | Sft | 950 | | - |
| 3 | **Surface Cleaning and Preparation:** Dismantling/Chipping, removal of the existing loose particles by grinding machine or wire brush, cleaning By Blower Machine & Water as per standard requirement for rooftop waterproofing work as per standard requirement. | Sft | 950 | | - |
| 4 | **Crack Repair for slab**: Supply & Apply of Low viscous epoxy injection resin grout Conbextra EP10M (Brand: Berger Fosroc) or, Equivalent Product &Thixotropic epoxy adhesive Nitobond PC (Brand: Berger Fosroc) for sealing crack and fixing injection nipples with Ancillary product, Injection machine, Injection series And Injected nipples. | Rft | 50 | | - |
| 5 | **Prime Coat**: Supply and apply primed by imported Bitumen primer -IMI@ 5 sqm/Liter. | Sft | 950 | | - |
| 6 | **Self-Adhesive membrane Waterproofing work**: Installation Self Adhesive Waterproofing Membrane Proofex Self Adhesive PR15 (Brand: Berger Fosroc) 1.5mm thick/Equivalent products of 1.5mm thickness Waterproofing membrane. Product Name: Proofex Self Adhesive PR15 Brand Name: (Brand: Berger Fosroc) | Sft | 950 | | - |
| 7 | **Re- Patent Stone Work:** Supply & application of floor surface leveling work with 70mm thick casting in average with the Cement: Sylhet sand & 15mm down Brick Chips with Admixture mortar. In ratio 1:2:4 | Sft | 950 | | - |
| | **Total amount (A)** | | | | - |
| **B. 'Internal road, Genset room and Car parking** | | | | | |
| 8 | **Taking out and Relaying** the existing HBB brick layer and edging after filling additional sand with comapction. | Sft | 150.00 | | - |
| 9 | **Sand filling** in foundation trenches and plinth with sand having minimum F.M. 0.8 in 150 mm layers including leveling, watering and compaction to achieve minimum dry density of 95% with optimum moisture content (Modified proctor test) by ramming each layer up to finished level as per design supplied by the design office only, all complete and accepted by the Engineer-in-charge. | cft | 300.00 | | - |
| 10 | **Supplying, fitting and fixing of CGI Color Sheet 0.32mm thick,** corrugated galvanized colour iron sheet (Bangladesh made)having minimum weight 50-53 kg per bundle (2'-6" width 70 – 72 rft long) roofing fitted and fixed on metal purlins with Approximately 13 roofing screws with sealing washer, rubber/m2, Nails, limpet washers, bitumen washers and putty etc. all complete as per design, drawing, speccification and direction of the E-I-C. CGI Color sheet: 7' long, 0.32mm thick, cost included roofing screw. | Sft | 50 | | - |
| 11 | **Supply and installation of MS angles** of sizes 40mm × 40mm × 3mm and 25mm × 25mm × 3mm with necessary cutting, shaping, weilding and fixing. Includes one coat of red oxide primer and one coat of enamel paint on all surfaces . Painting shall be completed before fixing CI sheets. | kg | 40 | | - |

8/10/26

8/10/26

Sr. Shelter & Construction Engineer
Population Movement Operation
Bangladesh Red Crescent Society

8/10/26

Dr. Mesbha Uddin Ahmed
Health & PSS Manager
Population Movement Operation
Bangladesh Red Crescent Society

# Bill of Quantity (BoQ)

## Treatment of Roof , Construction of Guide wall and Other Repairing & Miscellaneous works at MCHC, Teknaf.

| SL No. | Description of Items | Unit | Quantity | Unit Rate (BDT) | Amount (BDT) |
|---|---|---|---|---|---|
| 12 | **5" brick works:-** Supply and installation first class bricks with cement sand (F.M. 1.2) mortar (1:4) and making bond with connected walls including necessary scaffolding, raking out joints, cleaning and soaking the bricks for at least 24 hours before use and washing of sand, curing at least for 7 days all complete as per drawing and accepted by the Engineer or in-Charge.<br>**Note: Bricks are available at site. Only Cement and sand need to supply.** | Sft | 15 | | - |
| 13 | **RCC Works:** Providing and laying concrete (1:1.5:3) in ramp using cement, sand (F.M. 1.2), and first class brick chips. Includes mixing, casting, curing, and finishing, all complete as directed by the Engineer or facility in Charge. (Cement: CEM-II/B-M)<br>**Note: Brick chips and Rod are available at site. Only Cement and sand need to supply.** | cft | 15 | | - |
| 14 | **Cutting, uprooting, removing and stocking** Overgrown vegetaion | Lump sum | 1 | | - |
| | **Total amount (B)** | | | | - |
| **C. Wall and Ramp** | | | | | |
| 15 | **Supplying, fitting and fixing foreign made glazed wall tiles** complying BDS ISO 13006: 2015, irrespective of color &/or design, with 20 mm thick cement sand (F.M. 1.2) mortar (1:3) base and raking out the joints with white cement including cutting, laying and hire charge of machine and finishing with care etc. including water, electricity and other charges complete in all respect and accepted by the Engineer-in-charge. (Cement: CEM-II/B-M). The existing wall needs to prepare/clean properly before fixing tiles.<br>Glazed wall tiles 300 mm x 600 mm in sizes | Sft | 255 | | - |
| 16 | **Exterior standard acrylic emulsion paint** of approved best quality and color having water resisting properties and resistance properties against fungi, fading & flaking delivered from authorized local agent of the manufacturer in a sealed container; applying to exterior surface with surface preparation | Sft | 1750 | | - |
| 17 | **Minimum 12 mm thick cement sand (F.M. 1.2)** plaster (1:4) with fresh cement to both inner- and outer surface of wall, finishing the corner and edges including washing of sand, cleaning the surface, curing at least for 7 days, cost of water, electricity, scaffolding and other charges etc. all complete in all respect as per drawing and accepted by the Engineer-in charge. (Cement: CEM-II/B-M). Making Rough surface finishing on plastering works. | sft | 280 | | - |
| 18 | Repairing of insulation of existing glass roof | Sft | 1150 | | - |
| 19 | Reapairing of internal wall plaster and repainting | Sft | 100 | | - |
| 20 | Cleaning / Removing fungi from Carnice | sft | 750 | | - |
| | **Total amount (C)** | | | | - |
| **D. Guide wall (50 feet)** | | | | | |
| 21 | **Earthwork in excavation** in foundation trenches up to 1.5 m depth and maximum 10 m lead | cft | 560.00 | | - |
| 22 | **Backfilling and Compaction Works:** Necessary backfilling of excavated soil, with proper leveling, and compaction all complete as directed by the Engineer or facility in-Charge. | cft | 200.00 | | - |

8/10/26

8/10/26

Sr. Shelter & Construction Engineer
Population Movement Operation
Bangladesh Red Crescent Society

8/10/26

Dr. Mesbha Uddin Ahmed
Health & PSS Manager
Population Movement Operation
Bangladesh Red Crescent Society



Page 2 of 3

# Bill of Quantity (BoQ)

## Treatment of Roof , Construction of Guide wall and Other Repairing & Miscellaneous works at MCHC, Teknaf.

| SL No. | Description of Items | Unit | Quantity | Unit Rate (BDT) | Amount (BDT) |
|---|---|---|---|---|---|
| 23 | **Sand filling in foundation trenches** and plinth with sand having minimum F.M. 0.8 in 150 mm layers including leveling, watering and compaction to achieve minimum dry density of 95% with optimum moisture content (Modified proctor test) by ramming each layer up to finished level as per design supplied by the design office only, all complete and accepted by the Engineer-in-charge. | cft | 2,600.00 | | - |
| 24 | **Lean/ blinding concrete (1:3:6) in foundation** or in floor with cement, sand (F.M. 1.2) and picked jhama brick chips including breaking of chips, screening, mixing, laying, compacting to required level and curing for at least 7 days including the supply of water, electricity, costs of tools & plants and other charges etc. all complete and accepted by the Engineer-in-charge. (Cement: CEM-II/B-M) | cft | 30.00 | | - |
| 25 | **Shuttering works:-** Supply and installation of required wood, bamboo and hardware for Shuttering works to ensure the proper size and placement of concrete works in foundations as per drawing. | Sft | 25.00 | | - |
| 26 | **10",15" & 20" Brick works:-** Supply and installation first class bricks with cement sand (F.M. 1.2) mortar (1:4) and making bond with connected walls including necessary scaffolding, raking out joints, cleaning and soaking the bricks for at least 24 hours before use and washing of sand, curing at least for 7 days all complete as per drawing and accepted by the Engineer or in-Charge. | cft | 325.00 | | - |
| 27 | **Plaster and Net Cement Finish (NCF) Works:** Providing required materials and installation of plastering with a minimum 12-18mm thickness using sand and cement (1:4), Surface finished by net cement finishing (NCF). Works shall include all materials, proper floor leveling, curing, and all necessary charges to complete the plaster and smooth floor finish. | sft | 300.00 | | - |
| 28 | **Providing Weep holes** including pipes and brick chips | each | 30.00 | | - |
| 29 | **Providing and placing geotextile** (300 GSM and thickness 2.5mm ) at required location instructed by Engineer I/C. | sft | 1,800.00 | | - |
| 30 | **Supplying Geobags, filling geobags by sand** and placing at desired location. Geobag size 750x600 and weight 80 kg | each | 500.00 | | - |
| 31 | **Trees cutting and logging-**big size | each | 2.00 | | - |
| | **Total amount (D)** | | | | - |
| | **Grand Total amount (A+B+C+D)** | | | | - |

8/10/26
Md. Belal Hossain
Shelter & Const. Engr.
BDRCS, PMO
Cox's Bazar

8/10/2026
Mirza Abdul Hye
Sr. Shelter & Construction Engineer
Population Movement Operation
Bangladesh Red Crescent Society

8/10/26
Dr. Mesbha Uddin Ahmed
Health & PSS Manager
Population Movement Operation
Bangladesh Red Crescent Society